

**Vidyasagar Central Co-operative  
Bank Ltd., Midnapore**  
Head office: - Midnapore  
At & P.O. - Midnapore



Telephone - 9046177100 , 9046177146  
Website - [www.vidyasagarccb.bank.in](http://www.vidyasagarccb.bank.in)  
E-mail - [vccb@vidyasagarccb.bank.in](mailto:vccb@vidyasagarccb.bank.in)  
Dist. - Paschim Medinipur

**Memo No - Dev / 31**

**Date- 18/05/2026**

## **Notice Inviting e-tender**

**Notice inviting quotations (ITEM Rate) for Renovation of 10 nos. of ATM counters by Providing & fixing Vitrified Tiles, Carpentry, Interior Furnishing, False Ceiling, Electrical, LAN, stationary Goods AND ALLIED WORKS of Vidyasagar CCB Ltd.**

Sealed item rate quotations are hereby invited from reputed & experienced person /Supplier/Vendor.

**Name of work: - Esteemed Supplier/Vendor to Providing & fixing vitrified Tiles to the damaged / broken floors, supplying and fixing Carpentry, Interior Furnishing, False Ceiling, Electrical, LAN, stationary Goods, Glow sign Board and ALLIED WORKS at 10 nos. ATM premises of Vidyasagar CCB Ltd. Midnapore viz. Midnapore, Khargapur, Balichak, Turka, Mohanpur, Pratapdighi, Mongalamaro, Jhargram, Lalgah, Gopiballavpur.**

**Location & Place: 10 nos. of ATM premises as mentioned above**

**Completion time :- 60 days from the date of issue of Work Order .**

**Date of Physical visit of the Site :- 28.05.2026**

**Last date & time of submission of Quotation :- 01/ 06/ 2026 up to 4:00 PM**

**Date & time of Opening of Technical Bid :- 02/ 06/ 2026 at 3:00 pm**

**Date & time of Opening of Financial Bid :- 02/ 06/ 2026 at 3:30 pm**

### **Required Documents for Qualification in Technical Bid :**

- A.** Supporting documents should be submitted against their qualification and also will have to be submitted Professional Tax, Valid Trade license, PAN CARD, Income Tax return File for last 2 yrs., GST Registration Certificates.
- B.** The vendor / contractor who will be participating in the tender must possess a credential in similar type of work of at least 50% of their quoted amount with in last three financial year. If he / she failed to submit the credential, the bid may be rejected at anytime of the tender process.
- C.** All bid must be accompanied by a refundable earnest money / bid security amount of Rs.25000/- to the A/C No : 123005627958 (IFSC Code: WBSC0VCCB39) Vidyasagar Central Co- Operative Bank Ltd., Midnapore. **The EMD deposit is exempted for MSME vendors.**

**Continued to overleaf.....**

(2)

**Terms & condition :**

- A. It must be noted that the e-tender is an Item rate quotation. The quotation is comprises in two parts which may be awarded to the separate vendor if found suitable by the authority of the Bank.**
- B. The quotation should indicate specifically the basic price, taxes, other duties if any. No additional information will be entertained after due date.**
- C. Bidders who will successfully comply the technical Bid, will be eligible to compete in the price Bid.**
- D. No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.**
- E. No advance or running payment shall be made. Payment shall be released after the satisfactory completion of work.**
- F. All plywood materials must be of Approved Brand with BWR Grade (Water Resistant) , ISO certified (Test certificate to be Given), mandatorily of Century / Greenply make. All wooden Frame material must be well seasoned sal wood No other materials specifications will be allowed under any circumstances.**
- G. All Laminate / Mica must be of Greenlam/ Sunmica / Meriona make.**
- H. All Electrical items must be in conforming to the Brands as specified in the BOQ.**
- I. All fittings and accessories must be of Godrej make with at least two years maintenance and replacement warranty. For Floor spring , the vendor may choose other than the Godrej product prior to the approval of the Engineer of the Bank.**
- J. Ceiling Boards including supporting members must be of SAINT GOBAIN / ARMSTRONG make. No deviation in spacing of supporting members will be allowed while execution. The Gauge of Angle / Tee s must be in confirmative to the specification.**
- K. All ACP material must be of Aludecor make. The support aluminum channel / section must be of LYKA/ Armstrong / Sait Gobain make.**
- L. We only accept products which are directly manufactured by the companies not marketed by the companies.**
- M. 90% payment against the bill will be made after inspection, acceptance of delivery and successful completion of construction works and balance 10% will be paid after 6 months from the date of payment of the final bill. The scheduled works will have to be completed within specified time, if it is failed 5(Five) % will be deducted from bill amount and also security deposit will be forfeited.**

***Continued to overleaf.....***

(3)

- M.** Maintenance period shall be one year from the date of successfully completion of work. During this period the vendor will be liable for any defect in the work due to bad workmanship and all the defects shall be rectified by the vendor's own cost immediately. If the vendor fail to rectify / remove the defects within 7 (Seven) days from the time of its reporting, the bank will have the option to take assistance from any third party to solve the said defects. In that event, the entire cost for this repairing will have to be borne by the vendor.
- N.** It must be noted that the each vendor has to be participated in all items mentioned in the Price Bid.
- O.** The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.
- P.** All legal disputes shall be trialed under the jurisdiction of Kolkata High court.
- Q.** The Bank will have the liberty to deduct requisite amount of TDS from your bill.
- R.** Safety & Security measures are to be taken by the contractor solely. Bank will not be responsible for any kind of mishap during the aforesaid construction works.
- S.** Completion Certificate from the concerned Branch Officials/Manager have to be submitted at the time of submission of the final bill.
- T.** Bank's GST No- 19AAAV0691B1ZN and Company's GST No must be quoted in Tax Invoice Bill.

❖ **It must be noted here that the authority of the Bank may change the quantity of work of any item as well as may cancel any items while execution. The vendor can't claim the quantity in the quoted Bill of quantity. Final bill will be drawn on the basis of the joint measurement and calculation of exact work quantity .**

❖ **All price bid & Drawings are attached in a separate file.**

For further details please visit our website [www.vidyasagarccb.in](http://www.vidyasagarccb.in) or contact **P&D Section, H.O. Midnapore (Mob : 9046177146)** & mail id : [development@vidyasagrccb.in](mailto:development@vidyasagrccb.in) or see notice Board on working days from 10:00 AM to 5:00 PM of the Bank . You can also visit the e-tender portal [www.tenderwizard.com/eproc](http://www.tenderwizard.com/eproc).

**Date:- 18/05/2026**

  
**General Manager**



**Estimate for Renovation of 10 nos. ATM of Branches of Vidyasagar CCB Ltd.,  
Midnapore by interior finishing works like Wooden paneling and False ceiling  
including stationary goods & Electrical fittings work**

**Part -A (Vitrified Tile Work)**

SI No	Specifications	Unit	Qty	Unit Rate	Total Cost
1	Providing and Fixing 1st quality, polished 24" x 24 " vitrified tiled flooring of Johnson or equivalent make. Fixing in cement sand ratio 1: 5 in line and level inclusive of wastage, cutting and joints filling with white cement. Vitrified Tiles has to be " Milky white" , if not available " Ivory" can be used.	Sq ft	200		

**Part - B (Furniture & Carpentry Works)**

SI No	Specifications	Unit	Qty	Unit Rate	Total Cost
1	Providing and Fixing 12 mm Armstrong Type suspended false ceiling on metallic grid in line and level, GI intermediate channel (sub frames)of size 45mm and 0.5mm thk with two flange of 15mm each at 1200 mm center to center , GI hanger of size 25mm, 0.5mm thk at 1200mm center to center distance, joint filling & finishing with proper scraping , India Gypsum screws to be used, inclusive of all material and labour as instructed by Site in - charge and directed.	Sq ft	850		
2	Providing and applying of 2 coats of enamel/plastic paint to existing rolling shutter including cover	Sq ft	675		
3	Overall servicing and greasing.	LS	12		
4	Repairing external fixed glazing of 8 mm saint gobain or equivalent cleared class with 2.25" x 2.25" aluminium sections Black /white Powder coated on all 4 side (existing material).	Sq ft	210		
5	Glass door repairing & floor spring change (Godrej/Hardwn)	LS	10		
6	1.5" x 1" (Thickness of the Pipe) Aluminium box section with 3mm aluminium Composite panel with a 2'x2' framework on the backside with spacing not exceeding 600mm - Color is silver - Clading to be done on side wall of ATM room till 1 feet - Shutter boxing is also of the same ACP color.Including - Panelling LHS, RHS, Jamb (LHS,RHS), Latak, top Jamb, Calding, Shuter Boxing	Sq ft	100		
7	1.5" x 1" Alu Section with 2X2 feet frame, 3 mm ACP including 7' X 2' door. 1 ATM slot to be made. Provision for the 2nd ATM to be kept. The framing to be done accordingly - 3mm ACP sheet can be "silver" color. The fixing to be seamless instead of grooving. (1ft loby side shifting)	Sq ft	650		

*Prabir Adhikary*

8	Providing and fixing a wooden shelf of size 2'-00" x 3'-00" comprising of 18mm thick marine ply with ACP on top, and all the exposed sides of 18mm thickness of the ply, bottom with 3 coats of 1st grade enamel paint wire manager (circular slot) for passing cables, resting on strong metal L section frame	Unit	20		
9	P and F 4" powder coated aluminium louvers of Silver colour complete as directed. Louvers to have collar on all the four sides. (24 ft x 6 ft)	Unit	20		
10	ABC Type - fire extinguisher to be provided - 2KG Cap	Nos.	10		
11	Dust Bin, Size 12 inch high and 8 inch in diameter steel , Ms perforated powder coated Rubber gasket on the floor end of the bin, Bin grounded on the floor. Dustbin to be grouted (If grouting is a challenge then it has to be fixed in such a way that Dustbin theft are curtailed).	Nos.	10		
12	Providing footmat / door mat of size 3' X 2' of Approved Colour	Nos.	10		
13	Various hole grouting post renovation work	LS	10		
14	2 X 15A socket for ATM(from UPS point)	Nos.	10		
15	2' 0" x 2' 0" mirror optic fixtures (Philips / wipro or equivalent) ,ONE IN RAW POWER & ONE IN UPS POWER. 2 X 18W CFL to be used in each fixture	Nos.	20		
16	2 x 15W LED Spot lights, fixture with lamps of make GE,Philips, Wipro, Opelite, Crompton, Clipsal, Bajaj	Nos.	60		
17	Conducting for Electrical Wiring	Rmt	500		
18	Providing & fixing Philips / Wipro or equivalent TUBE lights/ LED for BACK ROOM	Nos.	10		
19	Glow sign board 5 ft 6 inch by 3 ft and lolipop 2 ft by 2 ft	Sq ft	300		
20	Demolition	LS	10		
21	AC drain pipe laying conceal	Rmt	50		
22	Painting in back room and on side wall - after cladding	Sq ft	300		

*Prabir Adhikari*



