

Vidyasagar Central Co-operative
Bank Ltd., Midnapore
Head office: - Midnapore
At & P.O. - Midnapore,



Telephone - 03222-275417, 275411
FAX - 03222 - 275411
E-mail - vccbmidnapore@gmail.com
Dist. - Paschim Medinipur

Memo No. Dev/72

Date: 02/09/2026

Notice Inviting e-tender

1. Notice inviting quotations for Renovation of newly constructed Belda Branch (Project-A) by Civil, Interior Furnishing, Modular Furniture, False Ceiling, Electrical, LAN, CCTV AND ALLIED WORKS.

Online bids are hereby invited from reputed & experienced person /Supplier/Vendor on e-tender platform (tenderwizard.com/eproc).

2. Name of work: - Esteemed Supplier/Vendor to Supplying and fixing Wooden Counter works, Inside Painting, Gypsum Board False ceiling, Interior Furnishing and fixing and installation of Electrical Points and A.C. points including LAN & CCTV at A) Newly constructed Belda Branch of the bank At- Deuli, PO: Belda, Dist: Paschim Medinipur.

3. Location & Place: Belda Branch, at- Deuli, P.O. Belda, Paschim Medinipur

- **Completion Time:** 40 days from the date of issue of the Work Order.
- **Date of Physical Site Visit:** 07.09.2026
- **Pre-bid Meeting with Aspiring Vendors (Online mode):** 09.09.2026
- **Last Date & Time for Submission of Quotation:** 22/09/2026 up to 4:00 PM
- **Date & Time of Opening Technical Bid:** 24/09/2026 at 3:00 PM
- **Date & Time of Opening Financial Bid:** 24/09/2026 at 3:30 PM

4. Name of the Consultant Architect & Electrical Engineer:

- | | |
|----------------------------------|----------------------------------|
| a) Saptarshi Sinha, M.Fine (RBU) | b) Sri Sourin Kumar Das |
| Architect & Interior Designer | Electrical Engineer & Consultant |
| Ghatal, Paschim Medinipur | Medinipur, Paschim Medinipur |

5. Required Documents for Qualification in Technical Bid:

- A. Supporting documents must be submitted to prove qualification. Bidders must also submit Professional Tax receipts, a valid Trade License, PAN Card, Income Tax Returns for the last 2 years, and GST Registration Certificates.
- B. The participating vendor/contractor must possess a credential for similar work worth at least 50% of their quoted amount within the last three financial years 2023- 24, 2024 - 25, 2025- 26.
- C. All bids must be accompanied by a refundable Earnest Money Deposit (EMD) / bid security amount of Rs. 50,000/-, deposited to A/C No: 123005627958 (IFSC Code: WBSC0VCCB39), Vidyasagar Central Co-operative Bank Ltd., Midnapore. MSME vendors are exempted from this EMD deposit, if proper documents submitted.

Continued overleaf...

(2)

All the documents mentioned in the clause 5(A), (B), (C) has to be submitted mandatorily, except this the bidder/bid will be declared technically disqualified and financial bid will not be opened for the vendor.

6. Financial Bid:

A. The bid must explicitly indicate the basic price, taxes and any other applicable duties. No additional financial details or modifications will be allowed after the due date.

B. Lowest bidder (L-1) for each of the project (Project-A or Project-B) has to be taken into the account separately.

7. Terms & Conditions:

- A. No revision of rates shall be allowed except for changes in taxes/charges levied and officially notified by the Central or State Government.
- B. No advance or running payments shall be made. Payment will only be released after the satisfactory completion of the work.
- C. All plywood materials must belong to an approved brand with BWR Grade (Boiling Water Resistant), be ISO certified (test certificate must be provided), and be mandatorily manufactured by Century or Greenply, not marketed by only. All frame materials must be 2"x1" hallow Aluminum Bar. No other material specifications will be allowed under any circumstances.
- D. All electrical items must strictly conform to the brands specified in the Bill of Quantities (BOQ).
- E. It is to be noted that, the newly acquired Belda Branch premises is entirely vacant now, hence work to be done accordingly.
- F. All fittings and accessories must be of Godrej make and come with at least a two-year maintenance and replacement warranty. For floor springs, the vendor may choose a non-Godrej brand subject to prior approval from the Bank's Engineer.
- G. Ceiling boards, including all supporting structural members, must be manufactured by Saint-Gobain. No deviation in the spacing of supporting members will be allowed during execution. The gauge of the angles/tees must strictly match the specifications.
- H. The Bank only accepts products that are directly manufactured by the respective companies, not products merely marketed by them.
- I. 90% payment against the bill will be made after inspection, acceptance of delivery, and successful completion of construction works. The balance 10% will be kept as security deposit and will be refunded only if no structural deficiencies is found after 12 months after the payment of the final bill. The scheduled works must be completed within the specified time; failure to do so will result in a 5% deduction from the bill amount and forfeiture of the security deposit.
- J. The maintenance (defect liability) period shall be one year from the date of successful completion of the work. During this period, the vendor will be liable for any defects arising from bad workmanship, and all defects must be rectified at the vendor's own cost immediately. If the vendor fails to rectify or remove the defects within 7 (seven) days of reporting, the Bank reserves the option to engage a third party to resolve the

Continued overleaf...

(3)

issues. In that event, the entire cost of repair will be borne by the vendor and the payment may be made from the Security Deposit kept with the bank. If security deposit falls short, the bank has the right to claim it as co-operative dues under WBCS Act.2006.


- K. Each participating vendor must bid for all items mentioned in the Price Bid.
- L. The undersigned is the accepting authority and reserves the right to reject any or all quotations without assigning any reason. The authority is not bound to accept the lowest tender from any bidder.
- M. All legal disputes shall be tried exclusively under the jurisdiction of the Calcutta High Court.
- N. The Bank reserves the right to deduct the requisite amount of TDS from the final bill.
- O. Safety and security measures must be taken solely by the contractor. The Bank will not be held responsible for any mishaps or accidents during the construction work.
- P. A Completion Certificate issued by the concerned Branch Officials/Manager must be submitted alongside the final bill which will be duly verified & authenticated by the aforementioned consultant Architect and Electrical Engineer as per tender.
- Q. The Bank's GST No. (19AAAV0691B1ZN) and the company's GST No. must be explicitly quoted on the Tax Invoice Bill.

❖ **It must be noted here that the authority of the Bank may change the quantity of work of any item as well as may cancel any items while execution. The vendor cannot claim the quantity in the quoted Bill of quantity. Final bill will be drawn on the basis of the joint measurement and calculation of exact work quantity.**

❖ **All price bid & Drawings are attached in a separate file.**

For further details please visit our website www.vidyasagarccb.bank.in or contact **P&D Section, H.O. Midnapore (Mob : 9046177146)** & mail id : development@vidyasagrccb.bank.in or see notice Board on working days from 10:00 AM to 5:00 PM of the Bank . You can also visit the e-tender portal www.tenderwizard.com/eproc.

Date: 02/09/2026


General Manager

925
M

QUOTATION OF INTERIOR DECORATION VIDYASAGAR CENTRAL CO-OPERATIVE BANK LTD. PASCHIM MEDINIPUR BELDA BRANCH									
SL	WORK TYPE	WORK SPECIFICATION (Detailed)	ITEM DETAIL & BRAND / SPECIFICATION	AREA (SQ FT)	RATE/ SQ FT (₹)	AMOUNT(₹)			
1	FALSE CEILING (DESIGN)	* Providing & fixing 12 mm thick Gypsum Board False Ceiling with Tray design as per drawing and direction of Engineer-in-Charge. * G.I. framework made of 0.55 mm thick Ceiling Section, Intermediate Channel & Perimeter Channel conforming to IS specification. * Framework suspended with G.I. suspension rods, cleats, soffit cleats, anchor fasteners and connecting clips complete. * Tray type false ceiling with required level difference and recessed border (tray) as per approved drawing and design. * Side drop / boxing made with 12 mm Gypsum Board, including all vertical faces, edge finishing and necessary framing. * All joints reinforced with paper tape and finished with Gyproc Jointing Compound/ Saint-Gobain Joint Filler to obtain a crack-free smooth surface. * Complete with corner beads, screws, accessories, cutting, finishing, sanding and making ready for primer & paint. * All materials and workmanship shall be executed as per manufacturer's specification and Engineer-in-Charge's direction.	12 MM GYPSUM BOARD FALSE CEILING (TRAY TYPE) * 12 mm Thick - Saint-Gobain/Gyproc / Boral Gypsum Board. * G.I. Framework- 0.55 mm Thick Ceiling Section, Intermediate Channel & Perimeter Channel. * Suspension System - - G.I. Suspension Rods, Cleats, Soffit Cleats, Fasteners & Connecting Clips. * Tray Type False Ceiling with recessed border as per drawing. * Joints treated with paper tape and Gyproc Jointing Compound / Saint-Gobain Joint Filler. * Complete with corner beads, screws, accessories, cutting, finishing, sanding & making ready for primer & paint.	1996					
2	PLYWOOD DECORATION & GLASS	*Plywood supplying, fitting & fixing of boiling water proof plywood conforming to IS: 710-1977 bonded with phenol formaldehyde synthetic resin conforming to IS: 848-1974 of approved make & brand. * Finishing as directed & specified. *Laminates supplying, fitting & fixing of decorative laminates conforming to IS: 2046: 1995 of approved make, brand, finish & thickness. •Particle Board/MDF/Ply boards with recommended/ approved adhesive. •Cost includes supporting framework, teak wood batten/ lipping, hardware fittings, fixing, finishing & labour. * All edges to be banded with matching PVC/ABS edge band (1 mm thick) for neat and durable finish. *Laminate to be pressed using hydraulic press for bubble-free finish. *Final surface to be clean, even, scratch-resistant & polished. *Thickness of Laminate : 1 mm.	PLYWOOD Greenply 710 Grade/ Century Sainik ADHESIVE Fevicol Hiper LAMINATES (1 mm Thick) Merino / Greenlam/ Century / Amulya HARDWARE FITTINGS Godrej/Hettich/ Hafele / O-Zone MODERN DESIGN TABLE (2.5' WIDTH) WITH KEYBOARD & DRAWER WARDROBE WITH HARDWARE FITTINGS PARTITION WORK WITH DOOR Aluminium Partition with both side 9 mm & 12 mm Plywood & Laminates Pasting GLASS 12 mm Thick Glass on Table (Demarcation & Cash Counter) PLYWOOD PANELING WORK Pillar (All Pillars) & Back Wall Paneling (4'x12 mm Plywood) & Laminates & Louvers TOUGHEN GLASS 12 MM etching TOUGHEN glass door & fixed partition on front with Ozone/ Hafele floor spring & fittings.	198	304	650	36	550	96
3	PUTTY, OIL PRIMER & COLOUR	* Primer: Applying interior grade Acrylic primer of approved quality on plastered/concrete surface old or new to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping & cleaning. *Colour: Applying Acrylic Emulsion Paint of approved make & brand on walls & ceiling including putty & paping in intermediate coats as per manufacturer's specification (Two conts).	ASIAN PAINTS OR ICI 1. Putty (Royal Wall Putty) 2. Primer (Acrylic Interior Primer) 3. Paint (ROYALE) (Two Coats as per Superintending Engineer's instructions)	4795					
4	CURTAIN	Zebra Blinds with all accessories & fixing.	Roman/Zebra Blinds (Per Window)	60					
6	SLIDING UPVC ALUMINUM WINDOWS	Providing & fixing of UPVC sliding window	Providing & fixing of uPVC white colour sliding window including 5 mm one way glass with minimum 5 years of warranty.	60					
7	ACP SHUTTER BOX COVER	PROVING AND FIXING EXISTING ROLLING SHUTTER COVER WITH IRON FRAME & 3 MM ACP SHEET & ACRYLIC LETTERING & BRANDING	ACP BRAND - ALUDECOR 3 MM WITH 5 YRS WARRANTY.	60					
NOTES: 1. All materials to be of approved make & brand. 2. All works will be executed as per approved drawings, specifications. 3. GST, Labour cess & other statutory charges extra as applicable. 4. Payment terms: As per bank's terms.									
				TOTAL (₹)		0			
				GST	18%	0			
				TOTAL INCLUDING 18% GST(₹)		0			

QUOTATION OF ELECTRICAL WORK					
VIDYASAGAR CENTRAL CO-OPERATIVE BANK LTD. PASCHIM MEDINIPUR					
BELDA BRANCH					
A	ELECTRICAL INSTALLATION WORK				
SL	WORK SPECIFICATION (Detailed)	QTY	UNIT	RATE/ UNIT (₹)	AMOUNT(₹)
1	Provision for Fixing I nos. single phase WBSEDCL Meter:i) Hylam/Bakelite Sheet; size: 1200mm x 600mm x 12mm (H x W x Thickness) -1 nosii) 415V; 100A porcelain Kit Kat Fuse unit --- 3 nos.iii) 415V; 100A nutral link I nos.[for LT Connection]	1	EACH		0.00
2	Supply & Delivery 1.1KV grade Al/XLPE/STA/PVC multi starnding cable as per choice of EIC. (Make - Polycab / Havells / RR Kabel / Gloster / KEI)				0.00
2.01	4 core 35 sqmm	35	Mtr		0.00
3	Laying of 4 core 35 sqmm cable on wall/surface incl. S & F MS saddles with earthing attachment in 2 x 10 SWG GI (Hot Dip) wire, making holes etc. as necy., mending good damages and painting.	35	Mtr		0.00
4	Supplying and fixing compression type gland complete with brass gland, brass ring & rubber ring for dust & moisture-proof entry of XLPE/PVC armoured cables as below :	2	EACH		0.00
5	Finishing the end of following XLPE/PVC armoured cables by crimping method incl. supplying and fixing solderless socket (Dowels make), tapes, anticorrosive paste & jointing materials :	2	Set		0.00
6	Supplying and fixing 415V, 100A TPN SFU with sheet steel enclosure on flat iron/angle iron frame on wall with nuts bolts etc incl. S & F 3 nos. DIN type HRC fuse as per rating. (Make-L&T/Havells/Standard/Siemens)	1	EACH		0.00
7	Supplying and fixing 415V, 125A TPN on load front operated Changeover switch with Sheet Steel enclosure on angle iron frame on wall with nuts bolts etc. (Make-L&T/Havells/Standard/Siemens)	1	SET		0.00
8	Supplying & fixing sheet metal (16 SWG) Iron Clad Busbar chambers on angle iron frame on wall, incl. earthing attachment and painting as required (As per Drawing no. 470 of PWD Specification Book - May 1991) suitable size 415V, 100/125A 4 bars with Sheet Metal Box.	1	SET		0.00
9	Supplying and fixing 415 V, 25-32A per way, 6 wayTPN MCBDB with SS enclosure double-door with IP-42/43 protection with 63A Four Pole Isolators as incomer and 18 non SPMCBS ('C' Curve, 10 kA) as outgoing, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment, 63A FP Isolator, 18 no. (25-32A) SPMCB. (Make-Legrand/Havells/Standard/ Siemens/L&T)	1	NO		0.00
10	Supplying and fixing 250 V, 6-10A per way, (2+12) SPN MCBDB with SS enclosure double-door with IP-42/43 protection with DP Isolators as incomer and SPMCBS ('C' Curve, 10kA) as outgoing, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing 32/40A DP Isolator, 12 attachment, SPMCB). (Make-Legrand/Havells/Standard/ Siemens/L&T)	2	NO		0.00
11	Supplying and fixing 250 V, 6-10A per way, (2+8) SPN MCBDB with SS enclosure double-door with IP-42/43 protection with DP isolators as incomer and SPMCBS ('C Curve, 10kA) as outgoing, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment, 32/40A DP Isolator, DB no. SPMCB), (Make-Legrand/Havells/Standard/ Siemens/L&T)	1	nos		0.00
12	Distribution wiring in 2 x 22/03 (1.5 sqmm) single core stranded 'FR PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR (Precision/Presto make), with 1x22/0.3 (1.5 sqm) single core stranded 'FR PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Modular type switch (Brand approved by EIC) fixed on Modular Gi switch board with top cover plate and 2 no suitable size "Ph & N copper bar & earthing attachment fixed on wall incl mending good damages to original finish. (a) Average run 9 mtr.	110	POINT		0.00
13	Description of Work Distribution wiring in 1.1 KV grade 22/0.3 (1.5 sqmm) single core stranded 'FR >VC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR' (Precision make), with 1.1 KV grade 1 x 22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC, to 6A 3 pin Modular type plug socket & switch (Brand approved by EIC) on 4 Module GI switch board with 3/4 Module top cover plate on wall incl. necy. connection making earthing attachment, painting and mending good damages to building works. (a) On Board	13	POINT		0.00

SL	WORK SPECIFICATION (Detailed)	QTY	UNIT	RATE/ UNIT (₹)	AMOUNT(₹)
14	Distribution wiring in 1.1 KV single core stranded 'FR' PVC insulated & unsheathed copper wire (approved make) in 20mm size PVC rigid conduit 'FR (approved make) incl. necy. fittings as required				0.00
14.01	2 x 1.5 mm² + 1 x 1.5 mm² ECC [Separate 5A Board]	120	RM		0.00
14.02	2x2.5 mm²+1x1.5 mm² as ECC [16A P.P.]	120	RM		0.00
14.03	2 x 4 sqmm + 1 x 2.5 sqmm ECC [AC Point]	210	RM		0.00
14.04	2x6.0 mm²+1x4.0 mm² as ECC [For SPN DB]	25	RM		0.00
14.05	4x10.0 mm²+2x6.0 mm² as ECC	6	RM		0.00
15	Finishing of the PVC insulated wire ends by socketting with pin/ring type copper sockets and insulated tapes etc., including supplying sockets, tapes.				0.00
15.01	1.5 sq mm	280	SET		0.00
15.02	2.5 sq mm	60	SET		0.00
15.03	4.00 sq mm	30	SET		0.00
15.04	6.00 sq m	25	SET		0.00
15.05	10.00 sqmm	10	SET		0.00
16	Supply & Fixing 240 V, 6 A, 3 pin Modular type plug socket (Brand approved by EIC) with 6A Modular type switch, without plug top on 4 Module GI Modular type switch board with 3 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	25	EACH		0.00
17	Supply & Fixing 240 V, 1 nos 6 A and 1 no 16A Modular type plug socket (Brand approved by EIC) with separate 1 no 6A & 1 no 16A Modular type switch, without plug top on 6/8 Module GI Modular type switch board with 6 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	16	EACH		0.00
18	Supply & Fixing 240 V, 2nos 6 A, 3 pin Modular type plug socket (Brand approved by EIC) with 2nos 6A Modular type switch, without plug top on 6/8 Module GI Modular type switch board with 6 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	2	EACH		0.00
19	Supply & Fixing 240 V, 3 nos 6 A modular type plug socket (Brand approved by EIC) with separate 1 no 16A Modular type switch, without plug top on 8 Module GI Modular type switch board with 8 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	2	EACH		0.00
20	Supply & Fixing 240 V, 16 A, 3 pin Modular type plug socket (Brand approved by EIC) with 16A Modular type switch, without plug top on 4 Module GI Modular type switch board with top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	8	EACH		0.00
21	Supply & Fixing 240 V, 25 A, Modular type starter (Approved Make) with 25A Modular switch type DP MCB (C Curve) and 4 Module GI Modular type switch board with 4 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	10	NOS		0.00
22	Supply & Fixing 240 V, 25 A, 3 pin Modular type plug socket (Approved Make), without plug top and switch with 2 Module GI Modular type switch board with top cover plate flushed in wall and making necy. connections with PVC Cu wire and earth continuity wire etc.	10	NOS		0.00
23	supplying fitting & fixing of Philips/Havells/goldmetal make 980 lumen 12-15 watt led panel light (cool white/day light)	100	NOS		0.00
24	supplying fitting & fixing of Philips/Havells/goldmetal make 6 watt 500 lumen COB spot light (3000k/warm white)	44	NOS		0.00
25	supplying fitting & fixing of ww 10w/m led rope lights with adaptor	270	RM		0.00
26	supplying ,fitting & fixing of 10w/m 1000lm/m,3000 k (warm white) profile lights with u shaped aluminium chanel & fibre cover & adaptor	10	RM		0.00
27	Supply & Fixing 240V, 16 inch WALL FAN on wall by S&F rag bolts, nuts & washers (6 mm dia x 62 mm long) or as reqd. incl. S&F 24/0.20 PVC insulated flexible copper wire 0.5 mt. length Orient/Crompton/Havells/Usha)	20	NOS		0.00
28	Supply and delivery of 230V 300mm (12") Exhaust fan with all necessary accessories, as directed by EIC. [Make: EPC Heavy Duty, Usha, CG, Bajaj or equiv Make]	2	NOS		0.00
29	Fixing only exhaust fan after making hole in wall and making good damages and smooth cement finish etc. as practicable as possible and providing necy. length of PVC insulated wire and making connection for exhaust of following diameter: (a) 30 cm (12")	2	nos		0.00

SL	WORK SPECIFICATION (Detailed)	QTY	UNIT	RATE/ UNIT (₹)	AMOUNT(₹)
30	Earthing with Copper plate (610x610x3mm size) having weight of 9.84 Kg and 1 No. 25x5mm Copper strip (3.20 mt long) & 1 no. 6 sqmm PVC insulated stranded Copper wire (4 Mt long) incl. S & F 15 mm dia GI pipe (ISI-Medium) protection (4 mt. long) to be filled with bitumen, partly under the ground level & partly above ground level to an average depth of 3.65 Mts. below the ground level and restoring the surface duly rammed incl. providing 3.0 mt long, 25 mm dia GI pipe (ISI-Medium) for periodic treatment, incl. providing masonry 2 Set 15,500.00 enclosure on the top of the earth electrode of overall size 86.36x86.36x46cm deep (below Ground level) complete with cemented brick work (1:6) of 25 cm width, duly plastered with cement mortar (inside) CI hinged inspection cover of size 36.56x35.56cm with locking arrangement, GI reducer and treatment of soil by using salt & charcoal or coke for plate electrode	2	set		0.00
31	Supply & Fixing cu earth bar 25mm x 6mm,(minimum 8 hole) on porcelain chair as per direction of EIC.	1	M		0.00
32	Connecting the cu earthing to earth busbar including S&F 20 mm x 3 mm cu flat strip on wall/floor with saddles as required and connection to equipments incl. drilling holes, with bolts, nuts, washers etc.	50	RM		0.00
33	Excavation of soil for installation of Earth Electrode and filling & ramming. (a) For Morrum Soil	6	CUM		0.00
34	Extra for treatment of soil by using salt & charcoal or coke for plate electrode	2	NOS		0.00
35	Extra for providing masonry enclosure on the top of the earth electrode of overall size 86.36 cm x 86.36 cm x 46 cm deep (below Ground level) complete with cemented brick work(1:6) of 25 cm width duly plastered with cement mortar (inside) CI hinged inspection cover of size 36.56 cm x 35.56 cm with locking arrangement, GI reducer including drilling of 46 nos. 12 mm dia holes on the GI pipe	2	NOS		0.00
			TOTAL	₹	0.00
			GST	18%	0.00
			TOTAL INCLUDING 18% GST ₹		0.00
			Say Rs.		0.00

Rupees Eight Lakhs Twenty Nine Thousand Eight Hundred Forty Only

B	COMPUTER, LAN,UPS & BIO-METRIC SYSTEM				
SL	WORK SPECIFICATION (Detailed)	QTY	UNIT	RATE/ UNIT (₹)	AMOUNT(₹)
1	Supplying and fixing 250 V, 6-10A per way, (2+12) SPN MCBDB with SS enclosure double-door with IP-42/43 protection with DP isolators as incomer and SPMCBs (C Curve, 10kA) as outgoing, concealed in wall after cutting the wall & mending good the damages to original finish incl. inter connection with suitable size of copper wire and neutral link & provision for earthing attachment. 32/40A DP isolator, 12 no spmcb) (make-Legrand/Havells/Standard/Siemens/L&T)	1	No		0.00
2	Supplying and fixing 2 Way MCB SS enclosure with iP-20/30 protection, powder coated provision with 5 & F 40A DP isolator, on wall & mending good the damages to original finish incl painting connection & provision for earthing attachment (UPS IN/OUT).	2	set		0.00
3	Supply & Fixing 240 V, 4 nos. 6A 3 pin Modular type plug socket with 4 no. 6A Modular type switch (Brand approved by EXC) 16A Modular switch type MCB (C Curve) and indicator without plug top on 2 row 18 Module to top cover plate flushed in wall incl S&F switch board and cover plate and making necy connections with PVC Cu wire and earth continuity wire etc.	15	nos		0.00
4	Distribution wiring in 1.1 KV single core stranded 'FR PVC insulated & unsheathed copper wire (approved make) in 20mm size PVC rigid conduit 'FR approved make) incl. necy, fittings as required				
4.01	2X2.5 mm²+ 1x1.5 mm² as ECC [Computer Board]	220	RM		0.00
4.02	2X6.0 mm² + 1x4.0 mm² as ECC [For SPN DB]	75	RM		0.00
5	Finishing of the PVC insulated wire ends by socketting with pin/ring type copper sockets and insulated tapes etc., including supplying sockets, tapes.				
5.01	1.5 sq mm	30	set		0.00
5.02	2.5 sq mm	60	set		0.00
5.03	4.0 sq mm	6	set		0.00
5.04	6.0 sq mm	16	set		0.00
6	Supplying & Drawing LAN cable (CAT6) (Brand approved by EIC) in PVC rigidconduit/ in polythene pipe embeded in wall with S & F the pipe as required.	305	RM		0.00
7	Supply & Fixing RJ45 sitable for CAT6 cable (Brand approved by EIC) with PVC 200 board and top cover plate on wall and making necessary connections & testing 15 Each as required.	15	each		0.00
8	Supply & Fixing RJ45 Connector Module Plugs sitable for CAT6 cable (Brand approved by EIC) and making necessary connections & testing as required.	30	each		0.00
9	Supply & Fixing 16 Port Gigabit Switch and making necy, connections with PVC 900 Cu wire and earth continuity wire etc. (Make-TP-Link)	1	each		0.00

SL	WORK SPECIFICATION (Detailed)	QTY	UNIT	RATE/ UNIT (₹)	AMOUNT(₹)
10	Supply & Fixing 4U van Rack Loaded Wall Mount. (Make-D-Link)	1	each		0.00
			TOTAL	₹	0.00
			GST	18%	0.00
		TOTAL INCLUDING 18% GST ₹			0.00
			Say Rs.		0.00

#NAME?

C	CCTV INSTALLATION				
SL	WORK SPECIFICATION (Detailed)	QTY	UNIT	RATE/ UNIT (₹)	AMOUNT(₹)
1	Supply & Fixing 16 Channel Network Video Recorder NVR and making necy. Connections. (Make- CP Plus	1	nos		0.00
2	Supply & Fixing 8TB Internal Hard Drive HDD and making necy. Connections. (Make- WD HDD 4TB)	1	nos		0.00
3	Supply & Fixing 8 Port PoE+ 2 Uplink Port CP-ANW-HPU8H2-N12 POE Switch with High Data Transfer, PoE watchdog AI Function and making necy Connections. (Make- CP Plus)	2	nos		0.00
4	Supplying & Drawing LAN cable (CAT6) (Brand approved by EIC) in PVC rigid conduit/ in polythene pipe embeded in wall with S & F the pipe as required.	305	mtr		0.00
5	Supply & Fixing RJ45 sitable for CAT6 cable (Brand approved by EIC) with PVC board and top cover plate on wall and making necessary connections & testing 15 as required.	15	each		0.00
6	Supply & Fixing RJ45 Connector Module Plugs sitable for CAT6 cable (Brand approved by EIC) and making necessary connections & testing as required.	30	each		0.00
7	Supply & Fixing 4U van Rack Loaded Wall Mount. (Make-D-Link)	1	each		0.00
8	Supply & Fixing Dome IP Camera (Make CP Plus or equivalent make approved by STQC).	15	each		0.00
		TOTAL		₹	0.00
			GST	18%	0.00
		TOTAL INCLUDING 18% GST ₹			0.00

#NAME?

TOTAL (A+B+C)=	0.00
-----------------------	-------------

Rupees Eleven Lakh(s) Sixty Two Thousand Five Hundred Seventy Two Only